



Item No	Description	Qty	Unit	Rate	Disc%	Amount
1	Damaged Cover Plate Repairing By Welding As Per Instruction Rewind / Overhaul 1 HP Induction, Low Speed Motor Carry out incoming inspection, completely dismantle and inspect, overhaul motor, rewind stator (low speed winding). stove, varnish and stove, remove surplus varnish from stator core, DE/NDE end shield bearing housing, machine, sleeve, secure and machine to bearing spec, new studs, paint etc.	4.00	num	53.00	53.00	99.64
2	Audit Fee	3.00	num	4,131.00	21.00	9,790.47
3	Fab & Supply Of Concrete Block Lifting Shaft Fabricated from Ø110mm x 1500mm long Carbon steel EN8 material. Both sides locking pin Ø25mm, lifting hook 40mm thick plate. Lifting beam fabricated from 200 x 200 x 56.2Kg/mtr x 1.5mtr long with 4 nos lifting hook 25mm thick as per your drawing.	3.00	nos	4,123.00	41.00	7,297.71
4	Fab Of Man Basket For Max. 2 Persons Size: 1.2mtr (L) x 1mtr (W) x 2.2mtr (H). All the sides of the basket should be covered with 4mm expandable mesh. 6mm chequered plate shall be provided at the bottom, 4mm expanded mesh shall be provided on the top. 4 nos of pad eyes should be provided	2.00	num	1,312.00	32.00	1,784.32
5	Pad Eye Replacing Of Skid. Fabrication of 4nos of pad eye, remove existing from supplied Generator skid and rewelding as per instruction. Modification Job Of Supplied Skid (ID# ET CLF 15 69). Reduce the pad eye hole size by bushing (4nos), make additional door on top lid, fabrication and welding 6mm thick floor plate inside and put 2 nos. of drain holes, etc. apply primer and paint on new floor plate as per instruction	1.00	nos	3,523.00	25.00	2,642.25
6	Water & Electricity Charges	2.00	num	4,134.00	32.00	5,622.24
7	Damaged Cover Plate Repairing By Welding As Per Instruction Rewind / Overhaul 1 HP Induction, Low Speed Motor Carry out incoming inspection, completely dismantle and inspect, overhaul motor, rewind stator (low speed winding). stove, varnish and stove, remove surplus varnish from stator core, DE/NDE end shield bearing housing, machine, sleeve, secure and machine to bearing spec, new studs, paint etc.	6.00	num	4,241.00	13.00	22,138.02
8	Bumber Assembly - Lower Arm Bush	4.00	num	424.00	13.00	1,475.52
9	Damaged Cover Plate Repairing By Welding As Per Instruction Rewind / Overhaul 1 HP Induction, Low Speed Motor Carry out incoming inspection, completely dismantle and inspect, overhaul motor, rewind stator (low speed winding). stove, varnish and stove, remove surplus varnish from stator core, DE/NDE end shield bearing housing, machine, sleeve, secure and machine to bearing spec, new studs, paint etc.	5.00	num	5,242.00	16.00	22,016.40
10	Fab & Supply Of Concrete Block Lifting Shaft Fabricated from Ø110mm x 1500mm long Carbon steel EN8 material. Both sides locking pin Ø25mm, lifting hook 40mm thick plate. Lifting beam fabricated from 200 x 200 x 56.2Kg/mtr x 1.5mtr long with 4 nos lifting hook 25mm thick as per your drawing.	4.00	num	524.00	24.00	1,592.96

Al Fuzail Engineering Services WLL

Quote Validity	validity	Net Quote Value	74,459.53
Currency	Qatar Riyals		
Amount in words	Qatari Riyals seventy four thousand four hundred fifty nine & fifty three Dirhams		